

# Specification for Shaft/Pit Construction

Pr9825



Unitywater

## Pr9825 - Specification for Shafts

### Documents Details

This document is only valid on the day it was printed.

### Version Review

Revision	Reviewed by	Approved by	Date approved	Change	Reason for Change
2.0	B.Maule	A.Schoenmaker	30/11/2016	Reference to Uw technical standards	Consistency requirements
3.0	G.Burnett	G.Burnett	02/10/2018	Review only	N/A

### Written Direction Control

Document Sponsor	Infrastructure Technical Standards Committee
Document Author (Owner)	Manager Capital Delivery, SIS
Subject Matter Expert	Project Services Unit Leader – Capital Delivery
References	Refer to Section 3

# Pr9825 - Specification for Shafts

## Contents

<b>1. Purpose .....</b>	<b>5</b>
<b>2. Scope.....</b>	<b>5</b>
<b>3. References .....</b>	<b>5</b>
<b>4. Definitions, Abbreviations, Acronyms .....</b>	<b>9</b>
<b>5. Project Preliminaries .....</b>	<b>11</b>
5.1 Approvals .....	11
Shaft/Pit Types .....	13
<b>6. Procurement.....</b>	<b>17</b>
6.2 Principal Supplied Materials.....	17
6.3 Storage and Security of Materials .....	17
6.4 Personnel .....	17
6.5 Plant.....	17
6.6 Materials.....	18
<b>7. Project Execution.....</b>	<b>18</b>
7.1 Site Setup.....	18
7.2 Existing Services .....	18
7.3 Dilapidation Reports .....	18
7.4 Monitoring and Reporting.....	19
Daily Site Record.....	19
Surface Settlement or Heave.....	19
7.5 General Earthworks .....	20
7.6 Shaft/Pit Construction .....	20
Excavation and Shaft/Pit Support.....	20
Protection and Access.....	20
Dewatering .....	20
Ventilation and Atmospheric Monitoring.....	21
Noise and Vibration Monitoring.....	21
Lighting.....	21
Temporary Shafts/pits .....	22
Construction Tolerances.....	22
<b>8. Project Completion and Handover.....</b>	<b>22</b>
8.1 Document Submittals.....	23
8.2 Post-Construction Dilapidation report.....	23

## Pr9825 - Specification for Shafts

---

9. Typical Shaft/Pit Construction Inspection and Test Plan (ITP).....23

### List of Tables

Table 1 – Design Drawing Requirement ..... 13  
Table 2 – Work Plans ..... 15  
Table 3 – Work Procedures ..... 15  
Table 4 – Safe Work Method Statements..... 16  
Table 5 – Shaft/Pit Construction Reporting..... 19  
Table 6 – Allowable construction tolerance .....22  
Table 7 – Inspection and Test Plan.....24

## Pr9825 - Specification for Shafts

---

### 1. Purpose

- 1.0.1 The intent of this Specification is to outline the minimum deliverables and standards that the contractor needs to comply with when constructing shafts/pits on Unitywater projects.
- 1.0.2 The purpose is to ensure consistency across all projects delivered by Unitywater and that the safety, quality, environmental and design objectives required by Unitywater are achieved.

### 2. Scope

- 2.0.1 This Specification defines the minimum technical requirements for shaft/pit construction works undertaken on Unitywater projects.
- 2.0.2 Shafts/pits are constructed to provide access below ground level which can be of permanent or temporary nature to suit the project requirements. A range of different shaft/pit construction techniques are available and will be selected to best suit the ground conditions and if applicable the trenchless construction methodology.

### 3. References

#### 3.1 General

- 3.1.1 All work carried out under this Specification shall comply in all aspects (i.e. in design, construction, testing and performance) in accordance with the;
- South East Queensland Water Supply and Sewerage Design and Construction Code (SEQ WS&S D&C Code) including:
    - SEQ WSA 02 – Sewerage Code of Australia;
    - SEQ IPAM List (SEQ approved Infrastructure Products and Materials List);
    - SEQ Asset Information Specification;
  - Unitywater's Technical Specifications, including but not limited to:
    - Pr9903 Specification for Building and Structural Works;
    - Pr9902 Specification for Civil and Earthworks;
    - Pr9787 Specification for Microtunneling/Pipejacking Construction;
    - Pr9693 Specification for Mechanical Installations;
  - The latest relevant Australian (AS), British (BS) and IEC Standards; and
  - Standards in the following sections.
- 3.1.2 Reference to specific clauses of the various codes is intended to highlight those points and shall not be taken to imply a lesser importance for all other applicable clauses.
- 3.1.3 All the works shall conform to the Rules and Regulations of the Statutory Authorities having jurisdiction over the Site.

## Pr9825 - Specification for Shafts

---

- 3.1.4 If the requirements of this Specification do not articulate with the minimum requirements of the statutory regulations and standards, the regulatory requirements are taken to apply. If the requirements of this Specification are more exacting than the minimum requirements of the statutory regulations and standards, the former shall apply.
- 3.1.5 All Materials, fittings, accessories and equipment supplied by the Contractor shall be new and the best obtainable of their kind and shall comply in all respects with the requirements of the relevant Standards Australia specifications.

### 3.2 Applicable Legislation and Regulation

- 3.2.1 At least the following legislation and related regulation shall apply:
- Work Health and Safety Act 2011* (Qld);
  - Work Health and Safety Regulation 2011* (Qld);
  - Water Supply (Safety and Reliability) Act 2008* (Qld);
  - Environmental Protection Act 1994* (Qld);
  - Queensland Building Services Authority Act 1991*;
  - Professional Engineers Act 2002*.

### 3.3 Codes of Practice (ratified by Legislation)

#### **SEQ Water Supply and Sewerage Design and Construction Code**

The SEQ Water Supply and Sewerage Design and Construction Code (SEQ WS & S D & C Code) is available via the SEQCODE website: [www.seqcode.com.au](http://www.seqcode.com.au).

### 3.4 Quality and Standards

- 3.4.1 Unless otherwise specified, the equipment covered by this Specification shall be designed, manufactured, installed and tested in accordance with the following, listed in order of precedence:
- The Project Contract documents;
  - Requirements of the Statutory Authorities having jurisdiction over all or part of the manufacture, installation or operation of the plant;
  - The SEQ WS & S D & C Code;
  - All relevant Australian and governing Queensland standards where applicable;
  - Water Services Australia (WSAA) National Codes.
- 3.4.2 In the absence of relevant SEQ WS&S D&C Code, WSAA or Australian codes or standards, relevant industry, international (ISO), European or British standards shall be followed. International standards shall take precedence over European or British standards. The Contractor shall obtain approval from the Superintendent prior to using any non-Australian standards not nominated in the equipment specifications, schedules, datasheets or associated drawings.
- 3.4.3 Where local or international standards do not exist, the manufacture and installation of equipment shall be in full compliance with the manufacturer's own recognised standards. Manufacturer's standards, where used, shall be submitted to the

## Pr9825 - Specification for Shafts

---

Superintendent by the Contractor for review and acceptance shall be obtained by the Contractor from the Superintendent prior to commencement of manufacture.

- 3.4.4 All equipment shall comply with relevant Federal and State Acts, Regulations and Codes including, but not necessarily limited to, the following:
- *Work Health and Safety Act 2011* (Qld);
  - *Work Health and Safety Regulation 2008* (Qld);
  - Work Health and Safety Queensland Codes of Practice, including but not limited to:
    - Queensland Workplace Health and Safety Queensland Code of Practice 2011 – Managing noise and Preventing Hearing Loss at Work;
    - Queensland Workplace Health and Safety Code of Practice 2013 – Excavation Work;
    - Queensland Workplace Health and Safety Code of Practice 2011 – Confined Spaces;
    - Queensland Workplace Health and Safety Code of Practice 2006 – Formwork;
    - Queensland Workplace Health and Safety Code of Practice 2006 – Mobile Crane;
    - Queensland Workplace Health and Safety Code of Practice 2009 – Scaffolding;
    - Queensland Workplace Health and Safety Code of Practice 2011 – Hazardous Chemicals;
    - Queensland Workplace Health and Safety Code of Practice 2003 – Tilt-up and Pre-cast Construction;
    - Queensland Workplace Health and Safety Code of Practice 2004 – Steel Construction.
- 3.4.5 The version of any applicable standard or regulation shall be the revision in place at the date of invitation of contract packages.
- 3.4.6 The Contractor shall have in place a dedicated quality system that conforms to ISO 9001.
- 3.4.7 Quality control procedures for management, inspection, review and evaluation of all materials, manufacture, workmanship and testing of all products shall be planned and implemented by appropriately skilled and qualified persons to ensure that requirements of the quality procedures are met and that high quality is maintained.
- 3.4.8 The Contractor shall ensure that all equipment supplied/installed under this Specification is the product of a manufacturer who is fully experienced, reputable, qualified and regularly engaged for at least five years in the manufacture of the equipment to be supplied/installed.

## Pr9825 - Specification for Shafts

### 3.5 International and Australian Standards

Standard	Title
Quality Systems	
AS 2990	Quality Systems for Engineering and Construction Projects
AS 3901	Quality Systems for Design/Development, Production, Installation and Servicing
AS 3902	Quality Systems for Production and Installation
AS 3903	Quality Systems for Final Inspection and Test
Materials and Workmanship	
AS 2887	Plastics Waste Fittings
AS 3500	Plumbing Code of Australia
AS 3706	Geotextiles – Methods of test
AS 4373	Pruning of Amenity Trees
AS 4799	Installation of underground utility services and pipelines within railway boundaries

### 3.6 Industry Guidelines

3.6.1 At least the following industry guidelines shall apply:

- Australasian Society for Trenchless Technology (2015) Specification for Microtunneling and Pipe Jacking, Rev 2, June 2015;
- Australasian Society for Trenchless Technology (2015) Specification for Microtunneling and Pipe Jacking, Rev 2, June 2015;
- Australasian Society for Trenchless Technology (2010) Specification for Horizontal Directional Drilling, Rev 2, Feb 2015; and
- Safe Work Australia Guide for Tunnelling Work 2013.

### 3.7 Principal/Standard Drawings

3.7.1 Where the form of Contract is 'Design and Construct' the Principal Drawings are a high level concept design of the Principal's Project Requirements. The Contractor is to use these drawings as a guide to base the preliminary and final design upon. The Principal Drawings will typically illustrate the following elements:

- Site constraints; and
- Shaft/pit locations.

3.7.2 Alternatively, where the form of Contract is a construct only the Principal Drawings are a prescriptive representation of exactly what is to be constructed under the Contract. These drawings will include the minimum information that the Contractor will require to build the works. Any changes required or ambiguities found must be discussed with the Principal immediately.



## Pr9825 - Specification for Shafts

### 4. Definitions, Abbreviations, Acronyms

Term	Definition
Act	The <i>QLD Workplace Health &amp; Safety Act (2011)</i> and associated Regulations (2011).
Alimak / Pegga Lift	A work elevator, hoist or platform that can be vertically raised to lift plant, equipment, materials and personnel, i.e. a lift.
Caisson	A large watertight chamber, open at the bottom, from which the water is kept out by air pressure and in which construction work may be carried out under water.
Contiguous Pile	Contiguous Piles are constructed with a gap between each pile, i.e. not interlocking.
Contingency Plan	A plan to mitigate the risk of an activity. The plan usually allows for backup procedures, emergency response, and post-disaster recovery.
Contract	The legally binding agreement between two or more parties for doing or not doing something specified.
Contractor	An organisation that is bound to carry out and complete the works under the Contract.
Drawings	Drawings prepared by the Designer(s) for the purpose of illustrating the design requirements for the works under the Contract.
Designer	A professional engineer (RPEQ) who is appointed by the Contractor to carry out design and to issue instructions regarding standards, specifications and techniques to be observed in the construction of this project.
Design Documentation	Drawings, Specifications and other Design Documentation (including design standards, design or durability reports and calculations) in computer readable and written forms prepared by the Designer for the purposes of the Trenchless works under the Contract.
Geotechnical Baseline Report (GBR)	The GBR describes the 'Ground Reference Conditions' at the location (alignment as shown in the GBR) of the proposed alignment. The Baseline Conditions presented in GBR represent what is assumed to be encountered for the purpose of defining 'indications of the Contract'. The provision of a baseline in the Contract is not a warranty that the baseline conditions will, in fact, be encountered. It is therefore not appropriate for the Principal or Contractor to conclude that baseline statements are warranties.
Geotechnical Data Report (GDR)	The GDR describes the factual ground conditions at the locations nominated in the GDR. Typically these are close to the proposed trenchless alignment. The conditions presented in the GDR represent what observed during field investigations by the suitably experienced geotechnical engineer engaged by the principal. The provision of this information is not a warranty that the conditions will, in fact, be encountered. It is therefore not appropriate for the Principal or Contractor to conclude that the geotechnical statements made are

## Pr9825 - Specification for Shafts

Term	Definition
	warranties.
Gin Wheel	A machine for raising or moving heavy weights, consisting of a tripod formed of poles united at the top, with a windlass, pulleys, ropes, etc.
Entry pit or Launch shaft	An excavation at the commencement point of a pipeline excavation, in which the pipeline excavation plant and other equipment are installed and from which pipeline excavation operations are carried out.
Lift (shaft/pit)	The incremental construction height completed as the shaft/pit progresses downward.
Operator	Suitably trained or qualified person who operates machinery, an instrument, or other equipment.
Permit	A document that controls an activity that is considered high and not able to be commenced without completing important requirements.
Plug	This is installed at the base of a shaft/pit to limit groundwater inflow. Often a concrete plug is poured as the shaft/pit base.
Principal	Unitywater
Principal Drawings	Drawings issued to the Contractor forming part of the Contract. These drawings are owned by the Principal and are to be used to guide or govern the work under the contract.
Project Manager	A person nominated by the Contractor responsible for the construction of the contract.
Exit pit or reception/receival shaft	An excavation at the completion point of a pipeline excavation, in which the pipeline excavation plant and other equipment are removed once pipeline excavation has been completed.
Red Line Drawings	Original, as constructed drawings marked up in red detailing the as-built data.
Safe Work Method Statement	A document summarising the work required for an activity. This document summarises the hazards and the required measures to control minimise safety risk.
Secant/Interlocking Pile	Secant piles are constructed so that there is an intersection of one pile with another.
Soldier Pile	In an excavation, a vertical member that supports horizontal sheeting and is supported by struts across the excavation and by embedment below the excavation.
Specification	This document, that specifies, in a complete, verifiable manner, the requirements, design, behaviour, or other characteristics of a system, component, product, result, or service and, often, the procedures for determining whether these provisions have been satisfied.
Superintendent	An individual appointed by the Principal to perform two functions: Be the Principal's agent for the works under the Contract. Administer the Contract fairly and perform certain certifier requirements.
Superintendent's	A person nominated by the Superintendent, to act on behalf of the

## Pr9825 - Specification for Shafts

Term	Definition
Representative	Superintendent
Trenchless Construction	Installation of new or replacement of underground infrastructure with minimal disruption to surface environment, traffic, business, and other activities.

Acronym	Description
ASTT	Australasian Society for Trenchless Technology
AS/NZS	Australian / New Zealand Standard
ASS	Acid Sulphate Soils
AS	Australian Standard
CCTV	Closed Circuit Television
DBYD	Dial Before You Dig
DMP	Dewatering Management Plan
GBR	Geotechnical Baseline Report
GDR	Geotechnical Data Report
ID	Inside Diameter
IFC	Issued for Construction
ISO	International Standards Organisation
ITP	Inspection and Test Plan
NATA	National Association of Testing Authorities
N/A	Not Applicable
OD	Outside Diameter
QA	Quality Assurance
RPEQ	Registered Professional Engineer Queensland
SWMS	Safe Work Method Statement

## 5. Project Preliminaries

### 5.1 Approvals

- 5.1.1 Project approvals are usually controlled by Unitywater, however, in some instances approvals may be the responsibility of the Contractor. The Contractor is to refer to the Project Specific Specification for required approvals.
- 5.1.2 No work is to begin on site preparation or shaft/pit construction activities until all relevant permits and approvals have been gained and signed off by the relevant authority. The following authorities may be required to authorise the works:
- Queensland Government Department of Transport and Main Roads;
  - Queensland Rail and/or other rail infrastructure owners;
  - Local Government; and

## Pr9825 - Specification for Shafts

---

- Private land owners.

5.1.3 The Contractor shall be required to adhere to any approval conditions that the Principal or asset owner specifies.

### 5.2 Shaft/Pit Design

5.2.1 The Contractor shall be responsible for the design and construction of all aspects for the shaft/pit construction works including any temporary works. All design assumptions regarding subsurface conditions, equipment requirements, groundwater and other factors are the responsibility of the Contractor and shall be fully documented.

5.2.2 Based on the alignment shown in the Principal Drawings, the Contractor shall design and size the shafts/pits to accommodate all temporary and permanent works.

5.2.3 The design is to be certified by a RPEQ engineer and shall be submitted to the Principal's Representative for review prior to commencement of work.

5.2.4 The Contractor shall not proceed with any work until the Contractor's design has been accepted by the Principal's Representative.

5.2.5 Acceptance of the Contractor's design by the Principal's Representative in no way diminishes the responsibility of the Contractor for the design.

5.2.6 The Contractor is responsible for submitting the following shaft/pit design elements for approval prior to commencing work:

- The design of all shafts/pits both temporary and/or permanent;
- The type, size, depth and location of each shaft/pit shall suit site conditions;
- The means of excavation and support for shaft/pit construction;
- The design and execution of the shaft/pit construction equipment and processes;
- The design of all temporary works associated with the shaft/pit construction;
- Where the permanent works are to accommodate shaft/pit construction, these shall be designed to ensure the permanent works are not damaged in operation;
- Collaboratively working with the Principal's permanent infrastructure functionality and permanent design team to ensure the intent of the overall project is achieved;
- The shaft/pit construction sequence needs to conform to the established settlement and/or heave allowance;
- Any design amendments necessary to ensure that the construction techniques proposed are in compliance with the permanent design;
- Where ground anchors are required, it shall be demonstrated that they are a removable type anchor.

5.2.7 The shaft/pit design shall take account of all potential impacts on all existing infrastructure and underground features, including but not limited to impacts from ground movement, seismic activity, clearance to features, settlement/heave and any changes in the groundwater table resulting from the works, either temporarily during construction or permanently as a result of the construction.

## Pr9825 - Specification for Shafts

- 5.2.8 All designs shall ensure the safe operation and use of plant, equipment and materials handling under all expected loadings such as ground pressure, superimposed loads and ramming or jacking forces.

Table 3 below outlines the required design drawings for the works under the Contract. It also details the RPEQ sign off.

**Table 1 – Design Drawing Requirement**

Drawing Details	Plan / Elevation	RPEQ Sign Off
Site Layout	Plan	<input type="checkbox"/>
Shaft/pit Construction	Plan + Elevation + Details	<input checked="" type="checkbox"/>
Shaft/pit Layout	Plan + Elevation	<input type="checkbox"/>

### Shaft/Pit Types

- 5.2.9 Shaft/pit sinking shall be carried out by a method suitable for the site including geological conditions, hydrology, trenchless construction technique, depth and final purpose.
- 5.2.10 Shaft/pit construction methods may include the following:
- Sheet piling or secant piling;
  - Bored Piers and Shotcrete or Soldier Piles and timber lagging;
  - Shoring boxes/Trench Shields;
  - Battered/Benched excavation;
  - Jacked wet or dry caisson with steel, precast segmental concrete or cast in-situ lining;
  - Underpinned precast segmentally lined caisson; and
  - Bolts, mesh and shotcrete.
- 5.2.11 All excavation work shall comply with the Unitywater *Specification for Civil and Earth Works* (Pr9902) in conjunction with the Queensland Code of Practice 2013 – Excavation Work. Excavation shall only proceed when the ground is sufficiently stable.
- 5.2.12 Where piling techniques are used best industry practice shall be followed as per AS2159 – Piling – Design and Installation.
- 5.2.13 Where shoring boxes are utilised best industry practice shall be adhered to as per AS47441 – Steel shoring and trench lining equipment.
- 5.2.14 Where work is done by a jacked caisson operation using precast concrete or prefabricated components a leading cutting edge may be required. These components shall be secured tightly and proven prior to sinking each stage.
- 5.2.15 When using cast in-situ caissons below the groundwater table the joints must be sealed sufficiently to limit groundwater inflow.
- 5.2.16 Where work is done by underpinning an adequately sized collar is required to support the hanging section until it is secured. One full unit of support shall be completed and secured prior to excavating the next stage. Preformed or precast rings shall be secured via grouting or similar prior to excavating the next stage.

## Pr9825 - Specification for Shafts

---

- 5.2.17 Where an annular space is created through the shaft/pit method, it shall be properly supported with an engineering lubrication fluid (usually bentonite) or similar during shaft/pit sinking. On completion the annular space of the shaft/pit shall be filled and sealed using appropriate measures to correspond with surrounding geology (usually with grout).
- 5.2.18 Where ground anchors are used, each anchor shall be proof tested to 125% of the design working load, unless an alternate testing regime is approved by the Principal's Representative. All anchors shall be capable of being re-tested at any time as directed by the Principal's Representative.

### Shaft/Pit Base

- 5.2.19 Shaft/pit bases shall be constructed and maintained to suit the temporary or permanent nature of the design. In the case of temporary shafts/pits the Contractor shall submit his proposals for the shaft/pit base structure taking account of ground and groundwater forces and sealing the shaft/pit against water entry. Water pressure shall not be allowed to build up under shaft/pit bases until the shaft/pit has sufficient resistance or strength to prevent flotation. The construction sequence shall be approved by the Principal.

### Temporary Works Design

- 5.2.20 The Contractor is responsible for submitting the design of all temporary works associated with shaft/pit construction. This includes but not limited to the following:
- Temporary shaft/pit design;
  - Shaft/pit formwork;
  - Crane pads;
  - Access and egress;
  - Loadings within vicinity of the shaft/pit;
  - Backfill of temporary shafts/pits;
  - Retrieval of temporary shafts/pits; and
  - Removal of ground anchors upon completing the works.
- 5.2.21 At all times shafts/pits shall be provided with safe primary and secondary means of access and egress. The Contractor shall take into account the effects of plant and equipment loadings within close proximity of the shafts/pits. At least one means of egress shall permit access for a stretcher and retrieval of an injured person.

### Dewatering Management Plan (DMP)

- 5.2.22 Dewatering will only be permitted if the Contractor can prove that the effect of dewatering will not adversely affect the works, nor cause ground settlements exceeding the allowable limit, nor damage other structures or property.
- 5.2.23 The Contractor shall develop a Dewatering Management Plan (DMP) for approval prior to construction. Where dewatering spears are used or the effects of dewatering may impact nearby structures, this Plan shall be approved by a suitably qualified engineer (RPEQ). This Plan shall provide details throughout each stage of construction including but not limited to the following:

## Pr9825 - Specification for Shafts

- Dewatering method;
- Layout;
- Sump and pump locations;
- Expected groundwater flow rates;
- Predicted pump rates;
- Pump types and capacity including standby equipment;
- Treatment and testing procedure of groundwater;
- Emergency plan;
- Risk assessment;
- Predicted ground settlement;
- Discharge location and approvals; and
- Any additional geotechnical and hydrogeological data required.

5.2.24 The Dewatering Management Plan shall be approved prior to commencing construction. This shall be developed in conjunction with the Settlement Monitoring and Risk and Contingency Management Plans.

### Design Collaboration

5.2.25 The Contractor and Principal shall collaboratively work to ensure that all shaft/pit design aspects have been adequately considered and analysed across the two key project phases: shaft/pit construction and the Infrastructure's permanent operation.

## 5.3 Governing Documentation

5.3.1 As a minimum and in addition to the documentation required in the Contract documentation, the Contractor must submit for approval the following governing documentation as outlined in Table 2, Table 3 and Table 4 below:

**Table 2 – Work Plans**

Plans	Submission
Settlement Monitoring Plan	4 weeks before work
Major Lift Plan(s)	1 week before lift
Plant Suitability and Maintenance Plan	4 weeks before work
Risk and Contingency Management Plan	4 weeks before work
Dewatering Management Plan	4 weeks before work
Shaft/Pit Construction Inspection and Test Plan	4 weeks before work
Noise and Vibration Management Plan	4 week before work

**Table 3 – Work Procedures**

Procedure	Submission
Site Establishment	4 weeks before work
Shaft/Pit construction	4 weeks before work
Temporary shaft/pit retrieval or removal (if applicable)	4 weeks before work

## Pr9825 - Specification for Shafts

**Table 4 – Safe Work Method Statements**

Safety Work Method Statements	Submission
Operation of a crane/excavator	4 weeks prior to works
Work at Heights	4 weeks prior to works
Work in a confined or restricted space (if applicable)	4 weeks prior to works
Hot Works	4 weeks prior to works
Work at night under artificial light	4 weeks prior to works
Lifting	4 weeks prior to works

### 5.4 Risk Assessment and Control

5.4.1 The Contractor is to prepare and implement an approved contingency plan dealing with the key project or shaft/pit construction risks identified. As a minimum the Contractor is to have defined plans complete with equipment and materials on standby to mitigate against the following shaft/pit construction risks:

- Shaft/pit collapse;
- Shaft/pit flooding;
- Major equipment mechanical failure;
- Encroach on existing services;
- Settlement or heave scenarios;
- Damage to property;
- Groundwater inflows; and
- Serious safety or environment incidents.

### 5.5 Geotechnical Information and Risk

5.5.1 A Geotechnical Data Report (GDR) will be carried out by the Principal for the project and be provided to the Contractor. The report will cover a minimum set of requirements / criteria to aid and guide the Contractor to assess the project and specifically make informed decisions with regards to:

- Equipment selection;
- Dewatering requirements;
- Shaft/pit type, construction methodology and size; and
- Time and cost.

5.5.2 The level of geotechnical investigation shall be determined by, but not limited to the following inputs:

- Proposed methodology;
- Local site geology;
- Local site hydrogeology; and
- Project capital value.



## Pr9825 - Specification for Shafts

---

- 5.5.3 The Contractor shall inform itself thoroughly and make its own deductions and conclusions as to the difficulty of maintaining required excavations and of doing other work affected by the geology and hydrogeology of the Site.
- 5.5.4 Where the Contractor considers it necessary that additional site or subsurface investigations are required, the Contractor shall bring this to the attention of the Principal's Representative in a timely manner.

## 6. Procurement

### 6.1 Approved Suppliers

- 6.1.1 The Contractor is to provide materials which have previously been approved for use as per the SEQ Water Supply and Sewerage Design and Construction Code Accepted Civil Products and Materials.
- 6.1.2 If the Contractor proposes to utilise non pre-approved products these are to be submitted to the Superintendent's Representative for consideration.

### 6.2 Principal Supplied Materials

- 6.2.1 The Contractor shall document the receipt of any Principal Supplied Materials formally with the Superintendent's Representative. The receipt of materials by the Contractor accepts the suitability of these products for inclusion in the Works.
- 6.2.2 All Principal Supplied materials shall be handled strictly in accordance with the manufacturer's written instructions at all times.

### 6.3 Storage and Security of Materials

- 6.3.1 The Contractor is to provide security for the Site and Works including the construction facilities, plant and equipment. Materials shall also be secured by the Contractor to prevent their removal by unauthorised personnel.

### 6.4 Personnel

- 6.4.1 Appropriately trained and experienced personnel are required for the delivery of the works. Details of key personnel experience shall be provided to the Superintendent's Representative for approval before the works commence.
- 6.4.2 A site supervisor who is thoroughly knowledgeable of the equipment and shaft/pit construction procedure is to be present at the job site at all times. The site supervisor is to be present to address immediate shaft/pit construction concerns, health and safety and environmental issues.

### 6.5 Plant

- 6.5.1 All shaft/pit construction operations shall be performed using specialist equipment. All plant and equipment must be of a good standard and the Superintendent's Representative shall be permitted to inspect the proposed plant. All plant must pass the Principal's equipment assessment/inspection criteria prior to site mobilisation. The key Principal's equipment assessment/inspection criteria are listed below:
- Plant/equipment is required to be in good safe working order;
  - Plant/equipment is required to have a good service history;
  - Plant/equipment is required to be fit for purpose.

## Pr9825 - Specification for Shafts

---

- 6.5.2 The Contractor's management plans and procedures must detail a system for daily checking and resolving of issues with the supplied plant and equipment. The Contractor must supply key critical spares to ensure that the all equipment achieves a 90% working availability target.

### 6.6 Materials

- 6.6.1 Permanent materials are to fully comply with this specification, the documents referenced herein and the relevant Australian Standard.
- 6.6.2 Materials used on site shall be used in accordance with the manufacturer's recommendations and instructions.
- 6.6.3 The Contractor shall prepare and submit material certificates for all permanent materials to be included in the works.

## 7. Project Execution

- 7.0.1 The Contractor shall maintain control of site operations at all times. The Contractor has ultimate responsibility for site safety, the environment, quality workmanship and the satisfactory completion of the work as authorised under the Contract.

### 7.1 Site Setup

- 7.1.1 The Contractor is to set shaft/pit sites up in accordance with the approved site layout drawing which, as a minimum, must cover the following key aspects:
- Perimeter fencing in the allowed location;
  - Site topsoil stockpile complete with erosion and sediment control;
  - Entry and exit points;
  - Pedestrian walkways and appropriate exclusion zones around cranes or moving plant;
  - Equipment locations and movement zones;
  - Any underground or overhead services and the appropriate exclusion zones;
  - Shaft/pit location;
  - Traffic guidance systems.

### 7.2 Existing Services

- 7.2.1 General Earthwork's requirements shall conform to the requirements of Unitywater's *Specification for Civil and Earthworks* (Pr9902).
- 7.2.2 Shaft/pit locations shall be positioned to maximise cover between all services both above and below ground.

### 7.3 Dilapidation Reports

- 7.3.1 The Contractor is responsible for all pre-construction and post-construction property assessments. These assessments shall be a means of determining whether and to what extent, damage has resulted from the Contractor's operations during the Works. Any damaged identified shall be made good at the Contractors expense.
- 7.3.2 As a minimum the dilapidation reports shall capture:

## Pr9825 - Specification for Shafts

- all work sites and any surrounding area likely to be impacted by the construction activities, including heavy vehicle traffic;
- A minimum distance of 3x the depth of any shaft measured radially from its perimeter;
- A minimum distance of 2x the depth to invert level measured from the centreline of any pipe installed by trenchless methods;
- Any area within the settlement trough or zone of influence as defined by the Contractors prediction of ground settlement.

7.3.3 The report must capture the condition of all aspects of the natural and built environment within the nominated areas, including but not limited to inside buildings, public utilities and plant, roadways and landscaping.

### 7.4 Monitoring and Reporting

7.4.1 A reporting and auditing schedule must be prepared as part of the approvals process prior to commencing the Works.

#### Daily Site Record

7.4.2 Records of all employees engaged on Site are to be maintained and be available for inspection by the Superintendent's Representative at any time. At each progress meeting the Contractor shall supply to the Superintendent's Representative a list showing the number of employees in the various trade categories.

7.4.3 Records are to be kept of all major plant items on Site. At each progress meeting the Superintendent's Representative shall be supplied with a list showing a description of the items of plant, hours worked, hours out of service and hours lost through weather during the preceding week.

7.4.4 Records shall be maintained describing the major works being carried out on Site for each day of the Works and be available for inspection by the Superintendent's Representative at any time (as per Table 5 below).

**Table 5 – Shaft/Pit Construction Reporting**

Shaft/pit Construction Record / Report	Details
Shaft/pit Excavation Records	Daily
Geological Records	Daily
Ground Support Records	Daily
Environmental Details (water treatment, noise, dust and sediment controls)	Weekly and immediately if there is a problem
Plant, Labour & Materials Used	Weekly

#### Surface Settlement or Heave

7.4.5 Information on the permissible subsidence or heave at the ground surface shall be provided considering the use of the area, structures and systems in the sphere of influence of the project, taking into consideration the subsoil and groundwater conditions and the depth of cover.

## Pr9825 - Specification for Shafts

---

### 7.5 General Earthworks

- 7.5.1 General earthworks requirements shall conform to the requirements of Unitywater's *Specification for Civil and Earthworks* (Pr9902).

### 7.6 Shaft/Pit Construction

- 7.6.1 All works are to be conducted within approved working hours. Any works requested outside of these hours shall be approved by the Principal's Representative.
- 7.6.2 All works shall be constructed in accordance with the relevant design drawings and standards. Any discrepancies shall be notified to the Principal's Representative as soon as practicable.

#### Excavation and Shaft/Pit Support

- 7.6.3 Safety and security of excavations is the responsibility of the Contractor at all times during the execution of the Contract.
- 7.6.4 Prior to excavation, the shaft/pit area shall be checked for any existing services or structures as per Clause 7.2.
- 7.6.5 Methods of excavation shall be provided to the Superintendents Representative for review and approval. Unless otherwise approved, the excavation sequence shall follow the drawings and specifications at all times.
- 7.6.6 The Contractor shall ensure that the ground is stable prior to excavating each stage. The Contractor shall guard against distortion of shaft/pit lining during construction and the possibility of shaft/pit settlement or uplift at an intermediate stage of construction.

#### Protection and Access

- 7.6.7 At all times shafts/pits shall be provided with safe primary and secondary means of access and egress. The Contractor shall limit working at heights during construction where practicable. Handrails and toe boards shall be installed around the shaft/pit perimeter for fall protection.
- 7.6.8 Access routes into site shall be clearly signed and maintained throughout the execution of the Contract. Safe designated pedestrian access shall be implemented and maintained throughout work site.
- 7.6.9 A system to record, identify and locate personnel in shafts/pits shall be developed and implemented by the Contractor where appropriate.
- 7.6.10 The Contractor shall provide shaft/pit safety covers (in addition to site fencing) when the site is unattended, unless approved by the Superintendent's Representative.

#### Dewatering

- 7.6.11 The Contractor shall adhere to the Dewatering Management Plan at all times as per Clause 5.2.23.
- 7.6.12 The Contractor shall implement best practice systems to control groundwater at all times.
- 7.6.13 Removal of groundwater shall not cause damage to the works nor third party property.

## Pr9825 - Specification for Shafts

---

- 7.6.14 No water shall be discharged without the necessary approvals in place. A sufficient number of pumps and sumps shall be available for use and in good working order at all times to limit the risk of shaft/pit flooding.

### Ventilation and Atmospheric Monitoring

- 7.6.15 A schedule of gases and pollutants to be tested including the frequency and method of testing shall be provided by the Contractor.
- 7.6.16 Shafts/pits shall be ventilated at all times to maintain an atmosphere fit for respiration and free from oxygen deficiency, toxic gases and dust. Ventilation shall also be used to maintain a safe working temperature. Ventilation ducts/bags shall be continuously extended during the immediate stages of excavation as required.
- 7.6.17 Atmospheric monitoring equipment shall be in good working order, calibrated and installed at all shaft/pit faces. Continuous monitoring shall be undertaken at the work front to ensure the quality of air is within acceptable limits.
- 7.6.18 Atmospheric monitoring shall be conducted and recorded regularly as agreed with the Superintendent's Representative.
- 7.6.19 In an event of a ventilation failure or atmospheric alarm the workforce must be immediately evacuated and shaft/pit assessed prior to re-entering.
- 7.6.20 In an event of a ventilation failure or atmospheric alarm the workforce must be immediately evacuated and shaft/pit assessed prior to re-entering.
- 7.6.21 Appropriate respiratory protective equipment shall be made available and used where required.
- 7.6.22 Smoking is forbidden in shafts/pits and confined spaces at all times.
- 7.6.23 Dust suppression systems shall be readily available for use when required. Dust extractors shall be installed in conjunction with fresh air fans if required.

### Noise and Vibration Monitoring

- 7.6.24 Construction methods shall be selected to minimise noise and vibration at all times.
- 7.6.25 Noise and vibration levels shall remain in compliance with the Queensland *Environmental Protection Regulation 2008* and Queensland *Environmental Protection (Noise) Policy 2008*.
- 7.6.26 Monitoring shall be conducted regularly with the results recorded and made available to the Superintendent's Representative.
- 7.6.27 Any plant and equipment exceeding the acceptable limits may be removed off site at Principals discretion.
- 7.6.28 Equipment such as large generators, liquid recyclers and pumps shall be fitted with suitable noise reduction enclosures. All mobile equipment shall be fitted with broadband type reversing "squawkers" where possible. Beeper type reversing alarms shall not be permitted for any night works or any use in residential areas.

### Lighting

- 7.6.29 Lighting shall be adequate for the safe operation of all plant and equipment at the work fronts.

## Pr9825 - Specification for Shafts

- 7.6.30 An alternative lighting source shall be available or installed in the event of a power failure.

### Temporary Shafts/pits

- 7.6.31 Backfill for temporary working shafts/pits shall comprise material approved by the Superintendent.
- 7.6.32 Where the Contractor wishes to recover temporary shaft/pit linings the structure shall be removed in safe stages as backfilling proceeds, taking care to maintain the safety and structural integrity of the remaining lining.
- 7.6.33 Where a temporary shaft/pit is not retrieved, the Contractor shall remove all structure/s to a minimum level of 1.5m below the existing surface level or as otherwise agreed with the Superintendent's Representative.
- 7.6.34 All excess spoil shall be disposed of by the Contractor.

### Construction Tolerances

- 7.6.35 All shafts/pits shall be installed in conformance with the horizontal and vertical alignment as shown on the drawings subject to the allowable construction tolerances as listed in Table 6 below unless otherwise detailed in the Project Specific Specification.

**Table 6 – Allowable construction tolerance**

No.	Shaft/pit Types	Tolerance Type	Shaft/pit Diameter < 5m	Shaft/pit Diameter > 5m
1.	Grouted segmental lining:	Line and level	± 35 mm	± 50 mm
2.	Cast-in-situ concrete lining:	Line and level	± 35 mm	± 50 mm
3.	Sprayed concrete lining:	Line and level	± 30 mm	± 75 mm
4.	Bored / Secant / Soldier Piles	Line and level	± 50 mm	± 100 mm
5.	All other Shafts/pits	Line and level	± 50 mm	± 100 mm
6.	All Shaft/pit types	Verticality	1:200	1:200

- 7.6.36 Where the shaft/pit is out of alignment, based upon the tolerances tabulated below, excavation is to stop immediately. The excavation shall not recommence until directed by the Superintendent's Representative. The Contractor is responsible for all corrective works and associated costs needed to correct the alignment of the shaft/pit.
- 7.6.37 Under no circumstances shall the Contractor take corrective action without the approval of the Superintendent's Representative.

## 8. Project Completion and Handover

- 8.0.1 Throughout the construction phase of the project the Contractor is to complete and submit all records mentioned in the above sections of this Specification. In addition to these documents, the Contractor is to submit the as-built package in hard copy and electronic format.

## Pr9825 - Specification for Shafts

---

- 8.0.2 The Contractor shall keep records of all operations and all such data as directed by the Superintendent's Representative. These records will form part of the As-Built data. As-Constructed details shall comply with the requirements of SEQ WS&S D&C Code – Asset Information Specification.
- 8.0.3 The Contractor is required to submit as-built records in CAD and ADAC format. The Contractor must also submit Red Line Drawings detailing all relevant as-built records.
- 8.0.4 All records are to be approved by the Superintendent's Representative and submitted in accordance with Unitywater specifications listed within the contract documentation.

### **8.1 Document Submittals**

- 8.1.1 The Contractor shall liaise closely with the Superintendent's Representative during the documentation of survey work and shall provide the Superintendent's Representative with adequate opportunity to verify any measurement or detail the Contractor considers necessary prior to the commencement of reinstatement operations.

### **8.2 Post-Construction Dilapidation report**

- 8.2.1 The Contractor is responsible for all pre-construction and post-construction property assessments. These assessments shall be a means of determining whether, and to what extent, damage has resulted from the Contractor's operations during the Works.

## **9. Typical Shaft/Pit Construction Inspection and Test Plan (ITP)**

- 9.0.1 The Contractor shall prepare and submit for approval by the Principal at least four (4) weeks prior to the commencement of the shaft/pit construction works, an Inspection and Test Plan (ITP) for the works in accordance with the requirements of the relevant specifications.
- 9.0.2 Table 7 below detail the typical activities that trigger a visual inspection, witness point verification or hold point release. This list is to be used as a minimum guide for the Contractor to develop their ITP.
- 9.0.3 The Contractor must provide the Principal at least 8hrs (business hours) notice of a required visual inspection, witness point verification or hold point release.

## Pr9825 - Specification for Shafts

**Table 7 – Inspection and Test Plan**

Project Elements	Activity	Contractor Responsibilities			Principal Responsibilities		
		Visual	Witness	Hold	Visual	Witness	Hold
Project Documentation	Company HSEQ System	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Project Safety Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Project Environmental Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Project Quality Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Project Traffic & Pedestrian Management Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Plant Suitability and Maintenance Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Dilapidation reports (pre- and post-construction)	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Noise and Vibration Management Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Dewatering Management Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Site Establishment Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Settlement Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Shaft/pit construction Procedure	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Lift Plans (Shaft/pit Plant & Equipment)	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Design Documentation	Crane Pad	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Shaft/pit	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Groundwater Flow Predictions	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Settlement / heave Calculations	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Project Execution	Site Set Up To Plan	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	Crane / Excavator Pad Installation To Design	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	Shaft/pit Mark Out To Design	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	Shaft/pit Built To Design	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Concrete / Precast / grouting quality records (if applicable)	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Groundwater Monitoring and Review	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>



## Pr9825 - Specification for Shafts

Project Elements	Activity	Contractor Responsibilities			Principal Responsibilities		
		Visual	Witness	Hold	Visual	Witness	Hold
	Settlement / Heave Monitoring And Review	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Commissioning And Hand Over	Red Line Drawing	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	As Built Survey	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Submission Of All Project Records/SEQ WS&S D&C Handover Deliverables	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>